

CITY OF NORTH LITTLE ROCK TIMBER CREEK CT. DRAINAGE IMPROVEMENTS NORTH LITTLE ROCK, ARKANSAS




CITY OF NORTH LITTLE ROCK
Parks & Recreation Department
2700 WILLOW STREET
NORTH LITTLE ROCK, AR 72114

TIMBER CREEK CT.
DRAINAGE IMPROVEMENTS

COVER SHEET
AND
INDEX OF SHEETS


Sheet Number
1

PROJECT AREA




**ARKANSAS
STATE MAP**

PROJECT SITE



LOCATION MAP

PROJECT AREA



**PULASKI
COUNTY MAP**

INDEX OF SHEETS	
SHEET	TITLE
1	COVER SHEET AND INDEX OF SHEETS
2	SITE PLAN DETAILS
3	CURB INLET DETAILS
4	ADS TRENCH INSTALLATION DETAIL (HP STORM)
5	6'X6' JUNCTION BOX DETAILS
6	MISC JUNCTION BOX DETAILS

City of North Little Rock
October 2020

GENERAL NOTES:

1. CONTRACTOR IS RESPONSIBLE FOR LOCATING EXISTING UTILITIES WITHIN IMPACTED AREAS THROUGH ARKANSAS ONE-CALL.
2. FLOWLINES WILL BE ESTABLISHED IN THE FIELD IN COORDINATION WITH CITY ENGINEER.
3. ANY IRRIGATION AFFECTED WILL BE BROUGHT BACK TO SAME WORKING CONDITION AS BEFORE CONSTRUCTION.

TIMBER CREEK CT.

EXIST. CURB INLET
REMOVE & INSTALL
CURB INLET PER DETAILS
ON SHEET 3.

IN PLACE 18" x 120' RCP.
REMOVE & INSTALL
30" x 120' ADS HP STORM PIPE.

IN PLACE 4' JUNCTION BOX.
REMOVE & INSTALL
6' x 6' JUNCTION BOX
H = 12'-0"

EXIST. 36" RCP.
RETAIN & MODIFY
AS NECESSARY FOR CONNECTION
TO NEW JUNCTION BOX.



CITY OF NORTH LITTLE ROCK
Engineering Department

NORTH LITTLE ROCK, AR

500 WEST 13TH STREET


72114

TIMBER CREEK CT.
DRAINAGE IMPROVEMENTS

SITE
PLAN
DETAILS


DATE: 10/2020
DESIGNED BY: DMC
DRAWN BY: DMC
SCALE: 1" = 20'

SHEET NUMBER
2




PLAN-REVISED CURB INLET
Scale 3/8" = 1'-0"

Note: Seal All Concrete Sawcut Joints w/ Masterbuilder's NPI Polyurethane Joint Sealant or Approved Equal.



SECTION A-A
Scale 1/2" = 1'-0"



SECTION B-B
Scale 3/8" = 1'-0"

30" φ ADS HP Storm Pipe



CITY OF NORTH LITTLE ROCK
Engineering Department
500 WEST 13TH STREET
NORTH LITTLE ROCK, AR 72114

TIMBER CREEK CT.
DRAINAGE IMPROVEMENTS


CURB INLET DETAILS

DATE: 10/2020
DESIGNED BY: DCW
DRAWN BY: DCW
SCALE: As Shown

SHEET NUMBER
3



HP STORM TRENCH INSTALLATION DETAIL



NOTES:

- ALL PIPE SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH ASTM D2321, "STANDARD PRACTICE FOR UNDERGROUND INSTALLATION OF THERMOPLASTIC PIPE FOR SEWERS AND OTHER GRAVITY FLOW APPLICATIONS", LATEST EDITION, WITH THE EXCEPTION THAT THE INITIAL BACKFILL MAY EXTEND TO THE CROWN OF THE PIPE. SOIL CLASSIFICATIONS ARE PER THE LATEST VERSION OF ASTM D2321. CLASS I/IV MATERIALS (MH, CH) AS DEFINED IN PREVIOUS VERSIONS OF ASTM D2321 ARE NOT APPROPRIATE BACKFILL MATERIALS.
- MEASURES SHOULD BE TAKEN TO PREVENT MIGRATION OF NATIVE FINES INTO BACKFILL MATERIAL, WHEN REQUIRED.
- FOUNDATION: WHERE THE TRENCH BOTTOM IS UNSTABLE, THE CONTRACTOR SHALL EXCAVATE TO A DEPTH REQUIRED BY THE ENGINEER AND REPLACE WITH SUITABLE MATERIAL AS SPECIFIED BY THE ENGINEER. AS AN ALTERNATIVE AND AT THE DISCRETION OF THE DESIGN ENGINEER, THE TRENCH BOTTOM MAY BE STABILIZED USING A GEOTEXTILE MATERIAL.
- BEDDING: SUITABLE MATERIAL SHALL BE CLASS I, II, III, OR IV. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. COMPACTION SHALL BE SPECIFIED BY THE ENGINEER IN ACCORDANCE WITH TABLE 3 FOR THE APPLICABLE FILL HEIGHTS LISTED. UNLESS OTHERWISE NOTED BY THE ENGINEER, MINIMUM BEDDING THICKNESS SHALL BE 4" (100mm) FOR 12"-24" (300mm-600mm) DIAMETER PIPE; 6" (150mm) FOR 30"-60" (750mm-1500mm) DIAMETER PIPE. THE MIDDLE 1/3 BENEATH THE PIPE INVERT SHALL BE LOOSELY PLACED. PLEASE NOTE, CLASS IV MATERIAL HAS LIMITED APPLICATION AND CAN BE DIFFICULT TO PLACE AND COMPACT; USE ONLY WITH THE APPROVAL OF A SOIL EXPERT.
- INITIAL BACKFILL: SUITABLE MATERIAL SHALL BE CLASS I, II, III, OR IV IN THE PIPE ZONE EXTENDING TO THE CROWN OF THE PIPE. THE CONTRACTOR SHALL PROVIDE DOCUMENTATION FOR MATERIAL SPECIFICATION TO ENGINEER. MATERIAL SHALL BE INSTALLED AS REQUIRED IN ASTM D2321, LATEST EDITION. COMPACTION SHALL BE SPECIFIED BY THE ENGINEER IN ACCORDANCE WITH TABLE 3 FOR THE APPLICABLE FILL HEIGHTS LISTED. PLEASE NOTE, CLASS IV MATERIAL HAS LIMITED APPLICATION AND CAN BE DIFFICULT TO PLACE AND COMPACT; USE ONLY WITH THE APPROVAL OF A SOIL EXPERT.
- MINIMUM COVER: MINIMUM COVER, H, IN NON-TRAFFIC APPLICATIONS (GRASS OR LANDSCAPE AREAS) IS 12" (300mm) FROM THE TOP OF PIPE TO GROUND SURFACE. ADDITIONAL COVER MAY BE REQUIRED TO PREVENT FLOTATION. FOR TRAFFIC APPLICATIONS, CLASS I OR II MATERIAL COMPACTED TO 90% SPD AND CLASS III COMPACTED TO 95% SPD IS REQUIRED. FOR TRAFFIC APPLICATIONS, MINIMUM COVER, H, IS 12" (300mm) UP TO 48" (1200mm) DIAMETER PIPE AND 24" (600mm) OF COVER FOR 60" (1500mm) DIAMETER PIPE, MEASURED FROM TOP OF PIPE TO BOTTOM OF FLEXIBLE PAVEMENT OR TO TOP OF RIGID PAVEMENT.
- FOR ADDITIONAL INFORMATION SEE TECHNICAL NOTE 2.04.

No. 57
Stone
or
Approved
Equal

TABLE 1, RECOMMENDED MINIMUM TRENCH WIDTHS

PIPE DIAM.	MIN. TRENCH WIDTH
12" (300mm)	30" (762mm)
15" (375mm)	34" (864mm)
18" (450mm)	39" (991mm)
24" (600mm)	48" (1219mm)
30" (750mm)	56" (1422mm)
36" (900mm)	64" (1626mm)
42" (1050mm)	72" (1829mm)
48" (1200mm)	80" (2032mm)
60" (1500mm)	96" (2438mm)

TABLE 2, MINIMUM RECOMMENDED COVER BASED ON VEHICLE LOADING CONDITIONS

PIPE DIAM.	SURFACE LIVE LOADING CONDITION	
	H-25	HEAVY CONSTRUCTION (75T AXLE LOAD) *
12" - 48" (300mm - 1200mm)	12" (305mm)	48" (1219mm)
60" (1500mm)	24" (610mm)	60" (1524mm)

*VEHICLES IN EXCESS OF 75T MAY REQUIRE ADDITIONAL COVER

TABLE 3, MAXIMUM COVER FOR ADS HP STORM PIPE, ft

PIPE DIA	CLASS I		CLASS II		CLASS III		CLASS IV	
	95%	90%	95%	90%	95%	90%	95%	90%
12" (300mm)	41 (12.5m)	28 (8.5m)	21 (6.4m)	16 (4.9m)	20 (6.1m)	16 (4.9m)	16 (4.9m)	16 (4.9m)
15" (375mm)	42 (12.8m)	29 (8.8m)	21 (6.4m)	16 (4.9m)	21 (6.4m)	16 (4.9m)	16 (4.9m)	16 (4.9m)
18" (450mm)	44 (13.4m)	30 (9.1m)	21 (6.4m)	16 (4.9m)	22 (6.7m)	17 (5.2m)	16 (4.9m)	16 (4.9m)
24" (600mm)	37 (11.3m)	26 (7.9m)	18 (5.5m)	14 (4.3m)	19 (5.8m)	14 (4.3m)	14 (4.3m)	14 (4.3m)
30" (750mm)	39 (11.9m)	27 (8.2m)	19 (5.8m)	14 (4.3m)	19 (5.8m)	15 (4.6m)	14 (4.3m)	14 (4.3m)
36" (900mm)	28 (8.5m)	20 (6.1m)	14 (4.3m)	10 (3.0m)	14 (4.3m)	11 (3.4m)	10 (3.0m)	10 (3.0m)
42" (1050mm)	30 (9.1m)	21 (6.4m)	14 (4.3m)	10 (3.0m)	15 (4.6m)	11 (3.4m)	10 (3.0m)	10 (3.0m)
48" (1200mm)	29 (8.8m)	20 (6.1m)	14 (4.3m)	9 (2.7m)	14 (4.3m)	10 (3.0m)	10 (3.0m)	10 (3.0m)
60" (1500mm)	29 (8.8m)	20 (6.1m)	14 (4.3m)	9 (2.7m)	14 (4.3m)	10 (3.0m)	9 (2.7m)	9 (2.7m)

FILL HEIGHT TABLE GENERATED USING AASHTO SECTION 12, LOAD RESISTANCE FACTOR DESIGN (LRFD) PROCEDURE WITH THE FOLLOWING ASSUMPTIONS:
NO HYDROSTATIC PRESSURE
UNIT WEIGHT OF SOIL (γs) = 120 PCF

REV.	DESCRIPTION	BY	MM/DD/YY	CHKD
6	REV. MAXIMUM COVER HEIGHTS	RWD	01/11/17	

© 2016 ADS, INC.

ADVANCED DRAINAGE SYSTEMS, INC. ("ADS") HAS PREPARED THIS DETAIL BASED ON INFORMATION PROVIDED TO ADS. THIS DRAWING IS INTENDED TO DEPICT THE COMPONENTS AS REQUESTED. ADS HAS NOT PERFORMED ANY ENGINEERING OR DESIGN SERVICES FOR THIS PROJECT, NOR HAS ADS INDEPENDENTLY VERIFIED THE INFORMATION SUPPLIED. THE INSTALLATION DETAILS PROVIDED HEREIN ARE GENERAL RECOMMENDATIONS AND ARE NOT SPECIFIC FOR THIS PROJECT. THE DESIGN ENGINEER SHALL REVIEW THESE DETAILS PRIOR TO CONSTRUCTION. IT IS THE DESIGN ENGINEER'S RESPONSIBILITY TO ENSURE THE DETAILS PROVIDED HEREIN MEETS OR EXCEEDS THE APPLICABLE NATIONAL, STATE, OR LOCAL REQUIREMENTS AND TO ENSURE THAT THE DETAILS PROVIDED HEREIN ARE ACCEPTABLE FOR THIS PROJECT.

TRENCH INSTALLATION
DETAIL (HP STORM)

DRAWING NUMBER: STD-101D



4640 TRUEMAN BLVD
HILLIARD, OHIO 43026

ADVANCED DRAINAGE SYSTEMS, INC.

JAB
01/29/09
NTS
1 OF 1



CITY OF NORTH LITTLE ROCK
Engineering Department
NORTH LITTLE ROCK, AR
500 WEST 13TH STREET
72114


TIMBER CREEK CT.
DRAINAGE IMPROVEMENTS

6'X6' JUNCTION
BOX DETAILS


DATE: 10/2020
DESIGNED BY: DCW
DRAWN BY: DCW
SCALE: As Shown

SHEET NUMBER

5




PLAN - 6'X6' CONC. JUNCTION BOX
Scale $\frac{3}{8}'' = 1'-0''$



SECTION B-B (TYP. WALL REINF.)
Scale $\frac{1}{2}'' = 1'-0''$

Note: Stormwater Drain
Pipes Not Shown
For Clarity.



Stabilize Foundation
w/ No. 57 Stone or
C-Balast. Coordinate
w/ City Engineer.

SECTION A-A
Scale $\frac{1}{2}'' = 1'-0''$

**R-6110 to R-6137 Series
Catch Basin Frame, Grate**




Illustrating R-6115

Dimensions in inches

Catalog No.	A	B	C	DD	E	F	G	H	Frame Type
Heavy Duty									
R-6110	21	2 1/2	18	20	27 1/2	5	1 3/8	1	Y
R-6111	23	1 1/4	20	22	29 3/4	4	1 3/8	1	Y
R-6112	23	1 3/4	21	22 3/4	30	4	1 1/2	1	Y
R-6113	24	1 5/8	22	25 1/4	30	4	3/4	1	W
R-6114	27	1 1/4	23 1/2	25 1/2	33 1/2	4	1 1/2	1	Y
R-6115	27	2 1/2	24	26	33 1/2	5	1 1/2	1	Y
R-6116	29	1 3/4	27	29	35	6	1	1	Y
R-6117	32 3/8	2	30	32 1/2	39 1/2	6	1 1/2	1	Y
R-6118	38	1 1/2	36	38	49	4 1/2	1	1	Y
Light Duty									
R-6130	20 1/2	5/8	18	22 1/2	24	2 1/2	1	1	W
R-6131	21 1/2	1	20	23 1/2	27	4	1/2	3/4	W
R-6132	24	3/4	22	23 1/4	30	3 1/2	1/2	1/2	Y
R-6133	25	1	22	23 1/4	28	6	1/2	1	Y
R-6134	26 5/8	3/4	25	26 1/4	31	4	7/8	3/4	Y
R-6136	31 3/4	3/4	30	31 1/2	36 1/2	6	1 1/4	1	Y
R-6137	33 1/2	3/4	32	33	37	4	1 1/4	1	Y

CATALOG NUMBER	GRATE TYPE	SQ. FT. OPEN	WEIR PERIMETER LINEAL FEET
R-6110	G	0.9	5.5
R-6111	G	1.2	6.0
R-6112	G	1.3	6.0
R-6113	G	0.9	6.3
R-6114	G	1.8	7.0
R-6115	G	1.6	7.1
R-6116	G	1.9	7.6
R-6117	G	2.4	8.5
R-6118	G	2.6	9.9
R-6130	G	0.8	5.4
R-6131	G	1.0	5.6
R-6132	G	1.3	6.3
R-6133	G	1.3	6.5
R-6134	G	1.5	6.9
R-6136	G	2.5	8.3
R-6137	G	2.7	8.8



MANHOLE / INLET STEPS

N.T.S.

STEPS SPECIFICATIONS:

- A. MANHOLE STEPS: CORROSION RESISTANT, COATED AND REINFORCED WITH STEEL PER ASTM C-478. STEEL REINFORCING MINIMUM 1/2" DIAMETER.
- B. CAPABLE OF SUPPORTING MINIMUM 300 lb. LOAD.
- C. NON-SLIP TEXTURED TREADS
- D. REQUIRED IN ALL STRUCTURES 3'-0" DEEP OR DEEPER, UNLESS SPECIFIED OTHERWISE.

*Neenah R-6118 Catch Basin Frame & Grate
or Approved Equal By City Engineering*



CITY OF NORTH LITTLE ROCK
 Engineering Department
 NORTH LITTLE ROCK, AR
 500 WEST 13TH STREET
 72114

**TIMBER CREEK CT.
DRAINAGE IMPROVEMENTS**

MISC. JUNCTION BOX DETAILS

DATE: 10/2020
 DESIGNED BY: DCW
 DRAWN BY: DCW
 SCALE: As Shown

SHEET NUMBER

6