



ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE	TOTAL
1	Site Preparation	LS	1.00	\$	\$
2	Unclassified Excavation	CY	1750	\$	\$
3	Borrow Material	CY	500	\$	\$
4	Topsoil	CY	750	\$	\$
5	Aggregate Base Course	Ton	3850	\$	\$
6	Tack Coat	Gal	132	\$	\$
7	ACHM Surface Course	Ton	485	\$	\$
8	Undercut	Ton	1850	\$	\$
9	Concrete Driveway (4" Thick), Standard Finish	SF	7762	\$	\$
10	Concrete Driveway (6" Thick), Standard Finish	SF	2291	\$	\$
11	Concrete Curb and Gutter (Class 1)	LF	2640	\$	\$
12	Concrete Sidewalk	SF	5971	\$	\$
13	<b>Curb Inlet Special (4'x10' Box)</b>	EA	1	\$	\$
14	Curb Inlet 4' Box	EA	5	\$	\$
15	<b>Curb Inlet Special (4'x6' Box)</b>	EA	1	\$	\$
16	Wing 4' Extension	EA	6	\$	\$
17	Rebuild Junction Box Top	EA	3	\$	\$
18	Reinforced Concrete Precast Box Culvert	LF	500	\$	\$
19	Storm Drain Pipe, RCP (18")	LF	387	\$	\$
20	Tie to Existing Concrete Pipe	EA	10	\$	\$
21	Tie to Existing Box Culvert	EA	5	\$	\$
22	Solid Sodding	SY	8800	\$	\$
23	Maintenance of Traffic	LS	1	\$	\$
24	Handrail	LF	50	\$	\$
25	Access Ramp	SF	320	\$	\$
26	Water for Dust Control	Gal	50000	\$	\$
27	Final Clean Up	LS	1	\$	\$
28	Erosion Control	LS	1	\$	\$
29	Trench & Excavation Safety	LS	1	\$	\$
30	Cold Milling Asphalt Pavement	SY	500	\$	\$

31	Thermoplastic Pavement Marking White (12")	LF	230	\$	\$
32	Miscellaneous (Mobilization, Demobilization, Bonds, Insurance, As-built Record Drawings, Any additional items not covered elsewhere to complete the project per the drawings and specifications	LS	1.00	\$	\$
<b>33</b>	<b>Extend Reinforced Concrete Box Culvert</b>	<b>EA</b>	<b>2</b>	<b>\$</b>	<b>\$</b>

**MEASUREMENT AND PAYMENT**

**Item Number 1 – Site Preparation**

1. Unit of measure: Lump sum
2. This item shall compensate the Contractor for all materials, tools, labor, and equipment required for site preparation. This item shall include any jobsite set up, temporary construction offices, temporary restroom facilities, and any other items necessary to prepare the project site for construction.
3. This item shall include demolition, removal and disposal of any fences, drainage structures or facilities, walls, or any other structures that may be required for completion of the project in accordance with the plans and specifications.
4. This item shall include development of a Storm Water Pollution Prevention Plan in accordance with Arkansas Department of Environmental Quality standards and execution of the Stormwater Pollution Prevention Plan by installation and maintenance of temporary silt fencing, inlet protection, and any other measures required to protect the site and adjacent properties from erosion and storm water pollution.
3. This item shall be eligible for payment on the first pay request after groundbreaking.

**Item Number 2 – Unclassified Excavation**

1. Unit of measure: Cubic Yard
2. This item shall compensate the Contractor for all materials, tools, labor, and equipment required to excavate, haul off, and perform any and all earthwork required to complete the project in accordance with the plans and specifications.